G. R. S. 59] GPB—15,000—22-7-14

GENERAL AND REVENUE SECRETARIAT.

1903
~~191~~ .
(Municipal)

P5

File No. 97 of 1903

Serial Nos. 1—2

P5
~~Papers Filed.~~

Month December 1903

SUBJECT.

Repair of a portion of the Guttahalli Road, Bangalore city

Indexed

PREVIOUS REFERENCES.	LATER REFERENCES.

Commissioner
P.S.

1903.

SECTION Annual From

FILE No. 97 & 1903

SERIAL No. 1 To

The President, 3-12-03
Municipal Commission;
Bangalore City.

The Secretary to the Government of
His Highness the Maharaja of Mysore,
Genl. & Rev. Departments,
Bangalore.

Dated 21st November
Despatched 1st December } 1903
Received

General No. 139
No.

Enclosures No. 2

Submitting for Sanction an —
estimate for the Special repair
of a portion of the New Guttahalli
Road amounting to Rs 945/—

---

1 4
3.12.03

X X

Fe. V. K. Urgent
Rs 5/12/03 Drafted 6.12.03

2 — 1

OFFICE OF THE MUNICIPAL COMMISSION;

No. 139 with 2 Encls

City Bangalore, 21st November 1903
1st December 3

FROM

THE PRESIDENT,
Municipal Commission,
Bangalore City.

To

The Secretary to the Government
of His Highness the Maharaja of Mysore,
General & Revenue Departments,
Bangalore.

SIR,

I have the honor to submit herewith for sanction an estimate in duplicate for the Special repair of a portion of the New Guttahalli road amounting to Rs 945/-. The estimate was passed by the Board at the meeting of the 19th Instant. The cost may be met out of the balance available in the current year's budget under "VIII Public Works – Roads Original"

I have the honor to be
Sir
Your most obedient Servant
Illegible
President

147 &
2

3

Gen. No. 8.] Re 582-1 CLASS ROAD.

DIVIS

THICKNESS OF ROAD—

B. Mun. 93] Estimate of the Expense of Re-forming. Main Gubbalhalli 2nd, 3rd & 4th Cross & Extn

Measurement. Length.	Breadth.	Area.	Total area.	ABSTRACT OF WORKS	Rate.	Per.	Amount.
				Collection of Materials			
5x220	3	1/2	275	Jelly Metal	2-1-0	Cyd.	567
5x220	5	1/2	153	Ground	0-12-0	Cyd	115
				Consolidation of Materials			
5x220	3	0	3300	Picking & forming	0-0-2	Syd	34
			275	Spreading Metal	0-6-0	Cyd	103
			153	Spreading ground	0-6-0	Cyd	57
5x220	5	1/2	38	Collecting sand & Spreading Sand	0-6-0	Cyd	14
5x220	2	1/2	153	Earth work	0-2-6	Cyd	29
				Total Charges			919
				Contingencies			26
				Grand Total Charges			945

945

Rate of last re-form—
Thickness and description of material last used—
Amount of estimate for last re-form—
Watered or not watered—

I hereby certify that I have carefully measured the work required to be done, and at present, so far as can be foreseen, everything for the work is included in the estimate.

Dated

Surveyor,
Division.

I have carefully examined this estimate at the site of work, and it appears to include everything for completing the work which I consider necessary

Dated

Municipal Engineer.

Rates examined by—

Calculated and checked by—

Date Bangalore 4th November 03

President.

5

Report

This road was not recorded during the last 6 years for want of funds. The gulli[illegible] requires reforming. The bridge & culvert 2 Nos and three Soldiers is formed for the same amount to record 2nd, 3rd, 4th 6th & 7th Offs for a small width of only 3 yards during this year. The other portions must lie over till next year.

Abhaynagar Kanungo

Dist Bhandara

100 —0

..... Division.

MAINTENANCE OF MUNICIPAL ROADS.

No. 16

Estimate of the Expense of Re-forming [illegible] Road 2 miles 3 fur 4 Chains

Budget Head— Roads original

Grant I (Public Works)—

Part II, Repairs—

(a) Communication—Re-form by Contract—

Amount of this estimate—Rs. 94 0

Sanctioned

Date

President.

N.B.—A statement showing the balance available should accompany each batch of estimates.

MGOPB—6-1-03—500

Budget grant 1899-1900

Amount expended up to 5/6

5

SECTION Annual Read

FILE No. 97/1903

SERIAL No. 2

Letter No 139 dt the 21st Jany 1903 from the Presdt of the Mysore Bangalore City, submitting for Sanction, an estimate for Rs 7467. for the Special repair of a portion of the new Cuttapalli road.

Order thereon. No 2246-7/54-52 d. 7. 31/12/03

D

The estimate received with the above is sanctioned the cost being met from the provision under "VIII Public Works (b) Roads ordinary" in the current years budget of the City Municipality

Secretary

31/12/03

To. The Presdt. Mill Comb, Bangalore City, returning the above bill & Estimate

The Comptr, Mysore City, Book with a Copy of the Estimate

+ Rs. 1 Sanctioned by the President
Estimate
Temp. Estimate blank